BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
SCHEDULE-B

NAME OF THE WORK: Improvements and asphalting to 10th cross (between 8th main and pipe line road) Bhuavneshwari nagara in Bagalagunte ward no. 14 Dasarahalli sub division

Sl. No	Description of work	Unit	Qty	Rate Quoted by Sri K.Jagadish	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 PW, P & IWTD -SR 2016-17)	Cum	615.00	78.18	Rupees Seventy Eight and Eighteen Paise Only
2	KSRRB M400-1 For Grading I material construction of granular sub-base by providing coarse graded crushed stone aggregates of Granite/ trap/basalt material spreading in uniform layers with motir grader on prepared surface mixing by a mix in place method with rotawater at OMC, and Compacting with vibratory roller to achieve the desired density, complete as per specifications.by mix in a Place method for course Graded Granular Sub Base Material as per 400-2 for grading I material . Page No 155/ Item No. 20.6.1 PWD SR 2016-17	Cum	205.00	1366.32	Rupees One Thousand Three Hundred Sixty Six and Thirty Two Paise Only
3	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2016-17, P.No.158, I No.20.18)	Cum	471.50	1590.39	Rupees One Thousand Five Hundred Ninety and Thirty Nine Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Divison
BBMP

4	Providing and applying primer coat with S.S. Bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWDSR 2016-17, P.No.161, I No.21.6)	Sqm	2050.00	24.79	Rupees Twenty Four and Seventy Nine Paise Only
5	Providing and laying bituminous concrete with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filter transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment. rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH Speicification clause no 500.9 complete in all respects complete as per specification no 509. using 40/60 TPH Capacity H.M.P With Mechanical paver Gr-II (30 mm to 45 mm) with 6% VG-30 Bitumen (p-164, lt 21.22.6) PWD SR 2016-17	Cum	92.25	6539.85	Rupees Six Thousand Five Hundred Thirty Nine and Eighty Five Paise Only
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 133 Item No. 17.1 PWD SR 2016-17	Cum	615.00	72.68	Rupees Seventy Two and Sixty Eight Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Divison
BBMP